

MUNICIPAL CORPORATION OF GREATER MUMBAI

PERMIT

No. 783340005 Dt. 24.04.2025

To,
BHARTI AIRTEL LTD,
Mr. SHRIKANT ,CHAVAN (Utility Engg.)
BLDG. NO.7,INTERFACE BUILDING,
LINK ROAD,
MALAD WEST,
MUMBAI-400064.

Sub:- PERMISSION FOR TRENCH LAYING CABLE AT NITU MANDAKE
ROAD

Ref:- 1) Circular No. MGC/F/1835 dated 17.11.2007
2) Your application No. 783340005 dt.08.04.2025
3) Demand Note under No. 783340005

Sir,

With reference to your request the following trench is permitted:-

- 1) Name of Road : NITU MANDAKE ROAD
- 2) Starting Point : POLE NO. YJS/005/023
- 3) End Point : MCGM MOTOR LODER CHOWKY(AAGARWADI JN.)
- 4) Length/Area of Trench : 136 Mtrs
 - a) Length of Trench on Carriageway : 136 Mtrs
 - b) Area of Trench on Footpath : Sq Mtrs
- 5) Date of Start : 25.04.2025
- 6) Date of Completion : 30.04.2025

Subject to the following conditions:-

1. On receipt of permission, you shall immediately start the excavation.
2. Above mentioned date of start and completion, length of Trench, start and end point of Trench shall not be changed under any circumstances.
3. Before starting the excavation, area shall be barricaded as per Annexure-11.
4. Utility shall display the board at the start and end of Trench and if the Trench is more than 100 Mtr. it shall also be displayed in between and at the junction. Board must display information such as (A) Name of agency. (B) Date of starting. (C) Date of completion. (D) Name of site engineer. (E) Contact no. (Mobile). (F) With a note that "Inconvenience caused is regretted".
5. Sufficient security guards and traffic wardens should be provided.
6. Water entrances and chambers having opening shall be properly covered to avoid entry of excavated earth in it.
7. Your Site in-charge shall submit the daily report to M.C.G.M engineer in a format as per Annexure-12.

8. Wherever required steel plate shall be provided on the Trench for crossing of vehicular and pedestrian traffic.
9. Reflector signs shall be provided all along the Trench.
10. If Trench is more than 300 Mtr. in length, you shall only undertake 300 Mtr. Trench at once, lay your services and clear the site for reinstatement and movement of traffic and then only further excavation shall be undertaken.
11. It is likely that in the same Trench, number of agencies / utilities may lay their services. Under such circumstances, you shall have absolute co-ordination and co-operation with each other.
12. All the excavated earth shall be transported at the same time to the identified sites approved by Ward Engineer.
13. In case of taking Trench across the carriageway at least 2 number of 300 mm. dia N.P. II Class Hume Pipe or equivalent with encasing of 1:2:4 concrete shall be laid for any future service. Also you shall lay your services through duct.
14. Simultaneously, work order for reinstatement is issued to Ward Contractor and he will take up the work on the date of completion of your work mentioned in this permit or in phases as per clause No.10 above.
15. The Site Engineer shall be available at all the time during progress of work.
16. On receipt of permit, you shall immediately contact all other utility intimating that you will be taking Trench along the particular stretch and also arrange all the resources required by you for expeditious completion of your work.
17. You shall note that penalty of Rs. 2500/- per day for delay up to 2 days then Rs. 5000/- per day for more than 2 days and up to 5 days thereafter for more than 5 days Rs. 10,000/- per day will be levied for carrying your work beyond permitted date of completion. Similarly for increase in length than permitted, the R.I. charges for excess length shall be recovered @ 1.5 times of the applicable R.I. charges & for change in start & end point penalty of Rs. 5000/- each is applicable. The penalty will also be levied separately for violation of various other conditions mentioned in this permit.
18. By virtue of any circumstances, you are unable to undertake excavation as per this permit; you shall immediately communicate to the undersign. Under the circumstances you shall note that same permit will not be granted in future.
19. Wherever the existing finish is with Paver Block or laquered colour Paver Block you shall not break / damage these blocks while excavation & shall see that almost 100% of the blocks are removed intact & handed over to Municipal Engineer / Ward CWC.
20. The permit is issued subject to abiding the terms and conditions of circulars at reference no. 02, 03 & 04 above .
21. Incase of on going project roads the excavation for trench shall be taken in co-ordination and consultation with concern Dy.Ch.(Roads).

Asst. Engineer (Maint) ME Ward.

**Copy to 1 : Account officer ME Ward.
2 : H.C.(Exp.) ME Ward.**

Asst. Engineer (Maint) ME Ward.

Note: This is an electronically generated document, hence doesn't require signature.